


PLAN VIEW


B-35979-A APPROACH COPING.
(2) PLACES, (OPTIONALLY SUPPLIED BY EWSCO)

B-35978-C CHECK BOLT BUMPER
(4) PLACES, OPTIONALLY SUPPLIED BY EWSCO

11' X 10' APPROACH APRON w/10" X 18" GRADE BEAM AT PERIMETER




SECTION A-A




DETAIL OF BULKHEAD INSTALLATION
NO SCALE

FOR COPING DETAIL SEE DWG B-35979-A
TWO REQUIRED -- ONE AT EACH END
(OPTIONALLY SUPPLIED BY EWSCO)

FOR BUMPER DETAIL SEE DWG B-35978-C
FOUR REQUIRED -- TWO AT EACH END
(OPTIONALLY SUPPLIED BY EWSCO)




SECTION B-B
ROTATED 90°; SCALE 1:16




SECTION THRU SHORT
3/4" PVC CONDUIT (10) REQ.

NO SCALE
CONTINUOUS RUN FROM LOAD CELL TO TOTALIZER LOCATION

3/4" PVC CONDUIT FROM LOAD CELL LOCATION TO TOTALIZER LOCATION (10) PLACES
ACCURATE LOCATION REQUIRED.



LOAD CELL BASE PLATE DETAIL
NO SCALE



SECTION C-C
SCALE 1:16

MATERIAL REQUIREMENTS		TOTAL WT. OF REBAR			5378	
CONCRETE:		4	22	4	4'-0" 2'-0" 2'-0"	59
APPROACHES	6.4 CU YD	3	4	5	10'-6"	44
FOUNDATION	34 CU YD	2	204	5	10'-6"	2234
REINFORCING:		1	102	5	28'-7" (26" MIN. OVERLAP)	3041
REBAR	5378 LB					
4X4/4-4WVF	220 SQ FT					
PIECE NO.	QTY	BAR SIZE	LENGTH & DESCRIPTION		WT.	

PRELIMINARY NOT FOR CONSTRUCTION. FOR ILLUSTRATION ONLY.

FOR NON COMMERCIAL SCALES PROVIDE AN APPROACH OF 2 FEET MINIMUM LENGTH WHICH IS LEVEL AND IN SAME PLANE AS THE PLATFORM.

FOR COMMERCIAL SCALES CHECK WITH LOCAL WEIGHTS AND MEASURES OFFICIALS BEFORE STARTING CONSTRUCTIONS.

NATIONAL INSTITUTE OF STANDARDS AND TECHNOLOGY (NIST) HANDBOOK 44 REQUIRES:

- A) A STRAIGHT APPROACH OF AT LEAST ONE-HALF THE LENGTH OF THE PLATFORM.
- B) NOT LESS THAN 10 FEET OF APPROACH ADJACENT TO THE PLATFORM TO BE CONSTRUCTED OF CONCRETE OR SIMILAR DURABLE MATERIAL AND BE LEVEL AND IN THE SAME PLANE AS THE PLATFORM.

- NOTES:
1. CONCRETE STRENGTH: 4,000 PSI @ 28 DAYS
 2. REINFORCING ROD: GRADE 60, 60,000 PSI, ASTM A615
 3. SOIL BEARING IS ASSUMED TO BE 2,000 LB/SQ FT. TO BE VERIFIED IN THE FIELD BY END USER.
 4. SLAB TO BE FLAT WITHIN 0.25" AND LEVEL WITHIN 0.13" PER 10 FT.
 5. APPROACH COPING(BULKHEAD) TO BE ON A COMMON PLANE WITHIN 0.25".
 6. TOP OF REBAR MUST BE PLACED TO CLEAR THE ANCHOR BOLTS.
 7. ANCHOR BOLTS ARE TO BE INSTALLED AFTER FOUNDATION HAS CURED.
 8. SEE SPEC. A499-364-2 FOR ON SITE SUBSURFACE CONDITIONS.
 9. THE LENGTH FOR REBAR NO. 1 IS MINIMUM FOR 102 PIECES LAPPED. LONGER LAPS AND/OR PIECES MAY BE USED. MINIMUM LAP IS 26".
 10. BASE PLATES ARE NOT GROUDED. IF GROUING IS REQUIRED ADD GROUT THICKNESS TO APPROACH DEPTH SHOWN.

ALL SHARP CORNERS AND EDGES TO BE BROKEN				EMERY WINSLOW SCALE COMPANY SEYMOUR, CT U.S.A. TERRE HAUTE, IN.	
UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES				MODEL H85-10080-10CD-TA 100 TON, 80' X 10' WFTA M.T.S. A.G. SLAB FOUNDATION	
MACHINING	FABRICATION	DATE	BY	DRAWN	DATE
±.01	±.13	05/05/09			
CHECKED	DATE	ACAD FILENAME:	T03216	SCALE	FIRST USED ON
		LAYERS USED:	ALL	1:32	D-73073

THIS DRAWING IS THE PROPERTY OF EMERY WINSLOW SCALE COMPANY SEYMOUR, CONNECTICUT. THE INFORMATION CONTAINED HEREIN IS CONFIDENTIAL AND IS NOT TO BE USED OR DISSEMINATED TO OTHERS WITHOUT THE EXPRESS WRITTEN CONSENT OF EMERY WINSLOW SCALE COMPANY.

FULL SIZE PLOT D-24X36