



PRELIMINARY NOT FOR  
CONSTRUCTION FOR  
ILLUSTRATION ONLY

- NOTES:
- CONCRETE TO BE REINFORCED WITH REBAR: #4 BARS (GRADE 60) 16" MAX. O/C EACH DIRECTION. REBAR CALCULATED USING 20FT LENGTHS. IF ADDITIONAL SPLICES REQUIRED, ADD 25IN OR 2.17LB OF REBAR PER SPLICE.
    - A) TOTAL REBAR LENGTH: 912 FT.
    - B) TOTAL REBAR WEIGHT: 609 LB.
    - C) TOTAL CONCRETE: 13.5 YD.

		ALL SHARP CORNERS AND EDGES TO BE BROKEN		EMERY WINSLOW SCALE COMPANY SEYMOUR, CT. U.S.A. TERRE HAUTE, IN.	
		UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES		TRUCK SCALE, 60 X 10 CONCRETE DECK 4 SECTION ROADWEIGH II HYDROSTATIC	
		MACHINING FABRICATION .XX: ± .XXX: ±			
LTR	DATE	BY	DRAWN: S.JAECKS	DATE: 01/07/2020	
THIS DRAWING IS THE PROPERTY OF EMERY WINSLOW SCALE COMPANY SEYMOUR, CONNECTICUT. THE INFORMATION CONTAINED HEREIN IS CONFIDENTIAL AND IS NOT TO BE USED OR DISSEMINATED TO OTHERS WITHOUT THE EXPRESS WRITTEN CONSENT OF EMERY WINSLOW SCALE COMPANY.			CHECKED:	DATE:	
			ACAD FILENAME:		
			LAYERS USED:		
SCALE	SHEET	DRAWING NO.	REV.		
N/A	1 OF 1	198818			